



SAC DECLARES THAT
Engineering Systems
Technology Establishment
Laboratory for Calibration -
Riyadh

Has been accredited to carry out
the tests mentioned in the
accompanying list according to
laboratory accreditation
regulations and
ISO \ IEC 17025 /2005

تشهد اللجنة السعودية للاعتماد بأن
مختبر مؤسسة تقنية الأنظمة الهندسية
للمعايير - الرياض

تم اعتماده لأداء الاختبارات المذكورة في
القائمة المرفقة مع هذه الشهادة ، وفقاً
لائحة اعتماد المختبرات والمواصفة
القياسية الدولية
أيزو/ اي سي 17025 / 2005 .

Certificate No :
Date of Issue :
Expiry Date:

N-C-00001
11/16/2016
10/14/2019

رقم الشهادة :
تاريخ الإصدار:
تاريخ الإنتهاء :

رئيس اللجنة
Chairman of (SAC)

سعد بن عثمان القصبي
Saad O. Alkasabi





مجال الاعتماد

الاسم : مختبر مؤسسة تقنية الأنظمة الهندسية
للمعايرة - الرياض رقم الشهادة : N-C-00001

تاريخ الانتهاء: 2019-10-14 تاريخ الاصدار : 2016-11-16

المدي	الموافقة	افضل امكانية لقياس	الكمية المقيدة	م
0 to 1000mm	Calibration of Calliper	±1.8µm	Internal Length External Length Depth	1
0 to 1000mm	Calibration of Micrometer	±1.8µm	Internal Length External Length Depth	2
0.03~1mm	Calibration of Feeler Gauge	±0.00058mm	External Length	3
0~25mm	Calibration of Dial Gauge	±0.00058mm	External Length	4
0~25mm	Calibration of Dial Test Indicator	±0.00058mm	External Length	5
15°~90°	Calibration of Angle Measuring Equipment	+0°00'08", - 0°00'05"	Angle	6
Class E2 1mg~20Kg Class F1 1g~200kg Class M1 1Kg~1300Kg	Calibration of Balance	±0.006mg ±0.007mg ±0.0065mg	mass	7
1.25Nm~1500Nm	Calibration of Torque Tool	0.085%	Torque	8
10kN~3000kN	Calibration of Force Measuring Instrument	0.08%	Force	9
-17~650°C	Calibration of Thermometer	±0.10°C	Temperature	10
-17~650°C	Calibration of RTD Sensor	±0.10°C	Temperature	11
-17~650°C	Calibration of Thermocouple Sensor	±0.10°C	Temperature	12



-17~650°C	Calibration of Temperature Recorder	±0.10°C	Temperature	13
-17~650°C	Calibration of Temperature Indicators	±0.10°C	Temperature	14
28~400°C	Calibration of Infrared Thermometer	±0.02°C	Temperature	15
-27.0~650.0°C	Calibration of Temperature Block Calibrator	±0.2°C	Temperature	16
0~±1050V 0~±1050V 0~1100A 0~±1100A 10Ω~1GΩ 10nF~1μF 0.1Hz~10MHz	Calibration of Multi-meter	±36ppm ±2Mv ±0.02% ±0.02% ±12ppm ±0.05% ±0.1ppm	AC Voltage DC Voltage AC Current DC Current Resistance Capacitance Frequency	17
0~±1050V 0~±1050V 0~1100A 0~±1100A 10Ω~1GΩ 10nF~1μF 0.1Hz~10MHz	Calibration of Clamp Meter	±36ppm ±2Mv ±0.02% ±0.02% ±12ppm ±0.05% ±0.1ppm	AC Voltage DC Voltage AC Current DC Current Resistance Capacitance Frequency	18
0~±1050V 0~±1050V 0~1100A 0~±1100A 10Ω~1GΩ 10nF~1μF 0.1Hz~10MHz	Calibration of Multifunction Process Calibrator	±36ppm ±2Mv ±0.02% ±0.02% ±12ppm ±0.05% ±0.1ppm	AC Voltage DC Voltage AC Current DC Current Resistance Capacitance Frequency	19
0~300V 0~±110V 0~±100mA	Calibration of Power Supply AC Voltage	±0.001V ±0.01mV ±0.002mA	DC Voltage DC Current	20
0~1100A 0~±1100A	Calibration of Ammeter	±0.02%	AC Current DC Current	21
0~±1050V 0~±1050V	Calibration of Voltmeter	±36ppm ±2Mv	AC Voltage DC Voltage	22
RPM 6~600,000 RPM	Calibration of Tachometer	0.01%	rpm	23
0~70MPa	Calibration of Pressure Gauge	±0.02%	Pressure	24



0~70MPa	Calibration of Vacuum Gauge	$\pm 0.02\%$	Pressure	25
-27~650°C 1mg~10Kg	Calibration of Ignition Furnace	$\pm 0.44^\circ\text{C}$ $\pm 0.006\text{mg}$	Temperature and Mass	26
0~150°C	Calibration of Oven	$\pm 0.44^\circ\text{C}$	Temperature	27
0~150°C	Calibration of Water Bath	$\pm 0.44^\circ\text{C}$	Temperature	28
0~0.72Kg/l 1.12~2.72Kg/l	Calibration of Nuclear GaugeDensity	± 0.032 ± 0.04	Moisture	29
0~1000mm	Verification of Los Angeles Abrasion Machine	$\pm 5.97\mu\text{m}$	Length (Internal & External)	30
0~1000mm	Verification of Mould	$\pm 5.97\mu\text{m}$	Length (Internal & External)	31
0~1000mm	Verification of Manual Rammer	$\pm 5.97\mu\text{m}$	External Length	32
0~1000mm	Verification of Liquid Limit Device	$\pm 5.97\mu\text{m}$	External Length	33
0~1000mm	Verification of Cone and Tamping Rod	$\pm 5.97\mu\text{m}$	External Length	34
0~1000mm	Verification of Sieve	$\pm 5.97\mu\text{m}$	External Length	35
0~1000mm	Verification of Mechanical Soil Compactor	$\pm 5.97\mu\text{m}$	External Length Mass	36
0~1000mm	Verification of Asphalt Compactor	$\pm 5.97\mu\text{m}$	External Length Mass	37
10~100kN	Verification of California Bearing Ratio Machine	$\pm 0.28\%$	Force	38

10~100kN	Verification of Marshall Machine	$\pm 0.28\%$	Force	39
0~1000mm	Verification of Penetration Apparatus	$\pm 5.97\mu m$	External Length Mass Angle	40
0~3000kN	Verification of Compression Machine	$\pm 0.08\%$	Force Flatness (Feeler Gauge)	41
0~70MPa 0~1000mm	Verification of Air Pressure Meter	$\pm 0.02\%$ $\pm 5.97\mu m$	Pressure External Length	42
0~1000mm	Verification of Pycnometer	$\pm 5.97\mu m$	External Length Internal Length	43
0~1000mm	Verification of Straight Edge	$\pm 5.97\mu m$	External Length Flatness (Feeler Gauge)	44
0~25mm 0~1000mm	Verification of Relative Density Soil Apparatus	$\pm 0.01mm$ $\pm 5.97\mu m$	External Length External Length	45
0~1000mm	Verification of Flakiness and Elongation Gauge	$\pm 5.97\mu m$	External Length	46

